

**Estimate Abstract**

**OD/370/3553/121193/426260/00063643 : Improvement of road with CC/Gr-II Metalling from RD Road to village at R.Sikabadi  
Block : Kolnara, Gram Panchayat : Badakhilapadar  
Created By: Babulu Hembram**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	16.77	Cubic Meter	240.77592	4037.8121784
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.26	Cubic Meter	825.880232	10951.17187632
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.77	Cubic Meter	5373.97343174	90121.53445028
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	9.555	Cubic Meter	6877.01034938	65709.833888326
5	<b>R.C.C. Work : AR0410b (centering and shuttering fRigid and smooth or R.C.C. works including false works and dismantling them after casting) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. stairs excluding landing but including railing details for 5 Sqm			
	13.26	Square Meter	918.337198106	12177.151246886

<b>Total Amount:</b>	182997.50364021
----------------------	-----------------

Provision for Contingency (+) @	1829.9750364021
---------------------------------	-----------------

Display Citizen Board (+) @	1700
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	186527.47867661
----------------------	-----------------

<b>Grand Net Total Amount</b>	186527.47867661
-------------------------------	-----------------

**Babulu Hembram**  
**JE**  
**Kolnara Block**

**SAMEER KUMAR RATHA**  
**AEE**  
**Kolnara Block**

**SMT REENA PRADHAN**  
**BDO**  
**Kolnara Block**