

**Estimate Abstract**

**OD/371/3565/121405/382474/00064252 : Construction of CC Road at Badkasibahal Uparasahi  
Block : Rairakhol, Gram Panchayat : Kukudabahali  
Created By:Hemangini Bhoi**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	34.800494435	Cubic Meter	240.77592	8379.121064042
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.9683263271	Cubic Meter	542.585332	12462.276965674
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.883529774	Cubic Meter	5381.0222278	80088.604542017
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	13.920197774	Cubic Meter	6863.1921576	95536.992194758
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	5.640888	Square Meter	216.23489289764	1219.7568125276

<b>Total Amount:</b>	197686.75157902
----------------------	-----------------

Provision for Contingency (+) @	988.4337578951
Display Citizen Board (+) @	1324

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	199999.18533691
----------------------	-----------------

<b>Grand Net Total Amount</b>	199999.18533692
-------------------------------	-----------------

**Hemangini Bhoi**  
**JE**  
**Rairakhol Block**

**Supriya Biswal**  
**AEE**  
**Rairakhol Block**

**Rajendra Senapati**  
**BDO**  
**Rairakhol Block**