

Estimate Abstract

**OD/346/3305/116248/393279/00064606 : repair and restoration of road from badal singh house to pwd road
Block : Nilgiri, Gram Panchayat : Narenpur
Created By:Putuli Singh**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1	Cubic Meter	240.77592	240.77592
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.18	Cubic Meter	921.527232	3851.98382976
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.92	Cubic Meter	5952.95623474	23335.588440181
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	2.4	Cubic Meter	7578.61886838	18188.685284112
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	7.68	Square Meter	216.23489289764	1660.6839774539

Total Amount:	47277.717451507
----------------------	-----------------

Provision for Contingency (+) @	480
Display Citizen Board (+) @	242

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	47999.717451507
----------------------	-----------------

Grand Net Total Amount	47999.717451507
-------------------------------	-----------------

Putuli Singh
JE
Nilgiri Block

M Mohanty
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block