

Estimate Abstract

OD/365/3487/120064/390705/00065389 : CONST. OF CC ROAD FROM CHEMA HOUSE TO PANI HOUSE AT PATPUR

Block : Badasahi, Gram Panchayat : Talapada

Created By: JAYSHREE ACHARYA

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.625	Cubic Meter	240.77592	872.81271
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.295	Cubic Meter	1720.629132	17713.87691394
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.76	Cubic Meter	6069.4400963	77446.055628788
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	10.15	Cubic Meter	7649.5061951	77642.487880265
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	23.2	Square Meter	216.23489289764	5016.6495152252

Total Amount:	178691.88264822
----------------------	-----------------

Provision for Contingency (+) @	1786.9188264822
---------------------------------	-----------------

Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	2053
Provision for survey investigation and quality control (+) @	0

Total Amount:	186531.8014747
----------------------	----------------

Grand Net Total Amount	186531.8014747
-------------------------------	----------------

JAYSHREE ACHARYA
JE
Badasahi Block

SEETA HANSDAH
AEE
Badasahi Block

BANAJA DAS
BDO
Badasahi Block