

**Estimate Abstract**

**OD/346/3308/116301/394212/00066573 : repair & renovation of kalasuni m.e. school.  
Block : Simulia, Gram Panchayat : Iswarpur  
Created By:SHRI SUNIL KUMAR PATEL**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) :</b> Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	45.825	Square Meter	100.34838709677	4598.4648387095
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.45625	Cubic Meter	1493.995232	17115.5828766
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.5825	Cubic Meter	6284.3299587	28797.942035743
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	3.436875	Cubic Meter	7707.5434009	26489.863225968
5	<b>Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	0.5655	Cubic Meter	5200.84721276	2941.0790988158
6	<b>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	1.49675	Cubic Meter	6745.5997098855	10096.476365771

7	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	1.507455	Quintal	8421.6029474	12695.187471073
8	<b>R.C.C. Work : AR0410d (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm			
	6.32	Square Meter	1047.3822930467	6619.4560920551
9	<b>Plastering : AR1014i (16mm thick cement Plaster in CM (1:6) over brick work in outside (outside)) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	22.724	Square Meter	257.35818989	5848.2075070604
10	<b>Other Building Items. : AR1902 (cement based wall putty (water based)) :</b> Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.			
	100.47	Square Meter	79.21834	7959.0666198
11	<b>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) :</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	132.245	Square Meter	71.83248932951	9499.487551381
12	<b>Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) :</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	132.245	Square Meter	94.7526285875	12530.561367554
13	<b>Flooring : AR0816 (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor) :</b> Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	47.025	Square Meter	1192.404149882	56072.805148201

14	<b>Flooring : AR0817a (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755)) :</b> Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge			
	4.395	Square Meter	1331.508879836	5851.9815268792
15	<b>Concrete : AR0317 (2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips) :</b> 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)			
	59.057	Square Meter	369.838993614	21841.581445862
16	<b>Iron Work : AR1703 (Iron work wrought and put up in trusses and record racks) :</b> Iron work wrought and put up in trusses and record racks including all cost of labour, material, machinery and T & P required for the work etc. as per direction of Engineer-in-Charge.			
	3.094	Quintal	13225.897572252	40920.927088548

<b>Total Amount:</b>	269878.67026002
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	1375
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	2746.32
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	274999.99026002
----------------------	-----------------

<b>Grand Net Total Amount</b>	274999.99026002
-------------------------------	-----------------

**SHRI SUNIL KUMAR PATEL**  
JE  
Simulia Block

**SAROJ TIGGA**  
AEE  
Simulia Block

**Saswati Sadual**  
BDO  
Simulia Block