

**Estimate Abstract**

**OD/346/3298/116059/393817/00066569 : R/R OF ROAD FROM TILOTTAMA MALIK HOUSE TO RD ROAD  
Block : Bahanaga, Gram Panchayat : Latharpentha  
Created By:NIMITA KUMAR BHOI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	0.7645536	Cubic Meter	240.77592	184.08609642931
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.104087616	Cubic Meter	1316.033232	4085.0824576957
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.12858944	Cubic Meter	6149.5374292	25388.91529108
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	11.0368764	Square Meter	216.39264180804	2388.2988415048
5	<b>Concrete : AR0307a (Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.36403584	Cubic Meter	7272.6013944	24465.291740796

<b>Total Amount:</b>	56511.674427505
----------------------	-----------------

Provision for Contingency (+) @	565.11674427505
Display Citizen Board (+) @	1500

Any Other Lumpsum (+) @	1423.2
Provision for survey investigation and quality control (+) @	
<b>Total Amount:</b>	59999.99117178
<b>Grand Net Total Amount</b>	59999.99117178

**NIMITA KUMAR BHOI**  
**JE**  
**Bahanaga Block**

**Laxmikant Das**  
**AEE**  
**Bahanaga Block**

**Subhashree Tudu**  
**BDO**  
**Bahanaga Block**