

Estimate Abstract

OD/370/3547/121123/425331/00065546 : CONSTRUCTION OF CC ROAD AT TADO
Block : Bissamcuttack, Gram Panchayat : Raskola
Created By:SAGAR GOUDA

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.8625	Cubic Meter	240.77592	3096.980271
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.8625	Cubic Meter	519.446232	6681.3771591
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	9.8	Square Meter	216.23489289764	2119.1019503969
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.725	Cubic Meter	5227.50850192	134477.65621189
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	21.86625	Cubic Meter	6806.69795304	148836.95911566

Total Amount:	295212.07470805
----------------------	-----------------

Provision for Contingency (+) @	2952.1207470805
Display Citizen Board (+) @	1835

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.19545513
----------------------	-----------------

Grand Net Total Amount	299999.19545513
-------------------------------	-----------------

SAGAR GOUDA
JE
Bissamcuttack Block

SRI RAMESH CHANDRA SAHU
AEE
Bissamcuttack Block

SRI SIBA PRASAD PATNAIK
BDO
Bissamcuttack Block