

Estimate Abstract

**OD/356/3397/118352/401313/00066998 : CONSTRUCTION OF CC ROAD RAMAKANTA MOHANTY HOUSE TO
Block : Dharmasala, Gram Panchayat : Mirjapur
Created By:SRADHANJALI MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.175	Cubic Meter	240.77592	523.687626
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.22	Cubic Meter	721.547232	3766.47655104
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.395	Cubic Meter	5844.34042266	43218.897425571
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	5.22	Cubic Meter	7293.44022142	38071.757955812
5	R.C.C. Work : AR0410d (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm			
	11.6	Square Meter	1047.3822930467	12149.634599342

Total Amount:	97730.454157765
----------------------	-----------------

Provision for Contingency (+) @	500
Display Citizen Board (+) @	1500

Any Other Lumpsum (+) @	268
Provision for survey investigation and quality control (+) @	1

Total Amount:	99999.454157765
----------------------	-----------------

Grand Net Total Amount	99999.454157765
-------------------------------	-----------------

SRADHANJALI MOHANTY
JE
Dharmasala Block

RAJAT KUMAR MOHAPATRA
AEE
Dharmasala Block

Jyotirmaya Kar
BDO
Dharmasala Block