

**Estimate Abstract**

**OD/346/3305/116254/393252/00018525 : Const. of C.C. Road from Bala Krushna Das House to Ananta Nayak House in Bauriora Dahisahi  
Block : Nilgiri, Gram Panchayat : Tentulia  
Created By:Ramesh Singh**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.64	Cubic Meter	240.77592	876.4243488
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.39	Cubic Meter	1053.029232	14100.06141648
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.87	Cubic Meter	6335.8945492	81542.962848204
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	9.62	Cubic Meter	7762.3887744	74674.180009728
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	36.4	Square Meter	216.23489289764	7870.9501014741
<b>Total Amount:</b>				179064.57872469
Provision for Contingency (+) @				1865

Display Citizen Board (+) @	2500
Any Other Lumpsum (+) @	3102.42
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	186531.99872469
----------------------	-----------------

<b>Grand Net Total Amount</b>	186531.99872469
-------------------------------	-----------------

**Ramesh Singh**  
JE  
Nilgiri Block

**Sarat kumar Upadhyay**  
AEE  
Nilgiri Block

**Bikram Kishore Parida**  
BDO  
Nilgiri Block