

**Estimate Abstract**

**OD/352/3349/117242/402548/00067802 : Repair & Maintenance of Dayanabili Market Complex  
Block : Bhuban, Gram Panchayat : Dayanabili  
Created By:Girish Kumar Parida**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.836634112	Cubic Meter	723.466232	15074.601168571
2	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.19495269248	Cubic Meter	6110.01794316	25631.23622176
3	<b>Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) :</b> 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaicion and direction of Engineer-in charge. (Old Work)			
	49.424396	Square Meter	762.3575358948	37679.060747649
4	<b>R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	0.6537782784	Cubic Meter	6278.3178017132	4104.6278036521
5	<b>Masonry Stone Work : AR0717 (Laterite stone masonry) :</b> Laterite stone masonry in cement mortar (1:6) in foundation and plinth cost conveyance, royalty, taxes of all materials, labor, required for the work, etc. complete and as per direction of the Engineer-in-charge.			
	2.3573736	Cubic Meter	5145.075167088	12128.864368909
6	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	127.09223303	Square Meter	246.716373572	31355.734842329

7	<b>R.C.C. Work : AR0410a (Centring &amp; Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height			
	10.312233	Square Meter	663.29946175911	6840.0985984345
8	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	0.0035	Quintal	8175.9788355	28.61592592425
9	<b>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) :</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	51.67729375	Square Meter	1012.8086648226	52339.210884583
10	<b>Painting : AR0918h (Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside).) :</b> Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	270.28827208	Square Meter	160.75408487694	43449.94383119
11	<b>Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) :</b> Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	13.86484372	Square Meter	230.37570221703	3194.1231081244

<b>Total Amount:</b>	231826.11750113
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	3000
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	12173
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	249999.11750113
----------------------	-----------------

<b>Grand Net Total Amount</b>	249999.11750113
-------------------------------	-----------------

**Girish Kumar Parida**  
**JE**  
**Bhuban Block**

**Ranjit Behera**  
**AEE**  
**Bhuban Block**

**Ayushi Mohapatra**  
**BDO**  
**Bhuban Block**