

Estimate Abstract

OD/356/3401/118454/400803/00066919 : RENOVATION OF GOPINATH JEW COMMUNITY CENTER

Block : Korei, Gram Panchayat : Mulapal

Created By: Bijay Kumar Nayak

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	10.382071552	Cubic Meter	240.77592	2499.7528294386
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.346274176	Cubic Meter	751.847232	10034.359296739
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.86482624	Cubic Meter	6015.07846836	29262.311568537
4	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	4.3072967648	Cubic Meter	5003.979051848	21553.622781152
5	Masonry Brick Work : AR0603ci (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	3.99644059776	Cubic Meter	4964.012038848	19838.379239822
6	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	2.35848361856	Cubic Meter	6563.2654358637	15479.354014746

7	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	1.3132410977664	Cubic Meter	7320.0875610054	9613.0398243609
8	R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	3.93392276672	Cubic Meter	14619.018823184	57510.090975632
9	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	3.2537291048064	Cubic Meter	12865.149840254	41859.71247293
10	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	9.648	Quintal	8438.6943795	81416.523373416
11	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	18.20527188	Square Meter	244.703326412	4454.8905872708
12	Plastering : AR1004i (12mm thick cement plaster (1:6) over Brick work in outside.) : 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	30.7137318	Square Meter	170.3512507672	5232.1226278583
13	Painting : AR0901dik (Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces (outer surface) (For repair and maintenance) .) : Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge(For repair and maintenance).			
	66.24355512	Square Meter	73.710682283871	4882.8576448044

14	Painting : AR0920k (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)(For Repair and maintenance)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For Repair and maintenance)			
	41.98843988	Square Meter	96.027979575	4032.0650471828
15	Painting : AR0918g (Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	48.03828324	Square Meter	156.64507673771	7524.9605644776
16	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	51.4218105	Square Meter	1007.4480793186	51804.80422331
17	Flooring : AR0817ab (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	5.7135345	Square Meter	1566.452238807	8949.978909026
18	Dismantling : AR1612 (Dismantling and removing 2.5 cm. thick artificial stone flooring) : Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	29.72896	Square Meter	100.34838709677	2983.2531860644
19	Painting : AR0901c (Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	27.70831975	Square Meter	68.99486536271	1911.7317905782
20	Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) : Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	27.70831975	Square Meter	94.763136375	2625.7272831914

21	Flooring : AR0816j (Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1) : Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	0.743224	Square Meter	950.7130758308	706.59277507127
22	Flooring : AR0817ap (Fixing Chequered Tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Chequered Tiles in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Chequered tiles including rubbing and polishing complete including cost of precast tiles.			
	1.393545	Square Meter	1086.10426255	1513.5351645552
23	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	38.63278352	Square Meter	189.3928249648	7316.7720071064

Total Amount:	393006.43818727
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	3930.0643818727
Display Citizen Board (+) @	3063
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	399999.50256914
----------------------	-----------------

Grand Net Total Amount	399999.50256914
-------------------------------	-----------------

Bijay Kumar Nayak
JE
Korei Block

SWAGAT KUMAR DASH
AEE
Korei Block

Abanikanta Sahoo
BDO
Korei Block