

Estimate Abstract

**OD/360/3441/119210/395706/00069606 : CONS PF CC ROAD FROM THAKURSAHI TO SCHOOL
Block : Rajkanika, Gram Panchayat : Barunadiha
Created By:PRATIBHA SAHOO**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	15.76	Cubic Meter	240.77592	3794.6284992
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.214	Cubic Meter	901.872632	11015.472327248
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.79	Cubic Meter	6247.46006626	86152.474313725
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	11.82	Cubic Meter	7739.53825362	91481.342157788
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	19.7	Square Meter	216.23489289764	4259.8273900835

Total Amount:	196703.74468805
----------------------	-----------------

Provision for Contingency (+) @	2000
Display Citizen Board (+) @	1296

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.74468805
----------------------	-----------------

Grand Net Total Amount	199999.74468805
-------------------------------	-----------------

PRATIBHA SAHOO
JE
Rajkanika Block

SUDHANSU SEKHAR PATRA
AEE
Rajkanika Block

KAILASH CHANDRA MAHALIK
BDO
Rajkanika Block