

Estimate Abstract

**OD/361/3452/119451/386053/00068268 : CONST. OF CC ROAD FROM UP SCHOOL TO TUKU MAHANTA HOUSE
Block : Kendujhar Sadar, Gram Panchayat : Bodapalasa
Created By: Manoj Kumar Sahoo**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.489062304	Cubic Meter	240.77592	1080.8581061829
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.93025509664	Cubic Meter	863.553232	14620.176507288
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.17065910432	Cubic Meter	5830.32036824	146753.00645794
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	16.2255264	Cubic Meter	7303.35452888	118500.7717169
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	49.32963494	Square Meter	216.23489289764	10666.788327931

Total Amount:	291621.60111625
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	4384

Any Other Lumpsum (+) @	994
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.60111625
Grand Net Total Amount	299999.60111625

Manoj Kumar Sahoo
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block