

Estimate Abstract

**OD/346/3305/116243/393095/00068187 : CONST OF CC ROAD FROM KARTIKA KHAMARI BADI TO PURIA
MAHALIK BADI
Block : Nilgiri, Gram Panchayat : Kanas
Created By:MADHUSMITA MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.04605376	Cubic Meter	240.77592	1214.9682364335
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.8201792	Cubic Meter	921.527232	15500.25317992
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	71.7396966	Square Meter	216.39264180804	15523.942469781
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.86623296	Cubic Meter	5971.6280502	130577.01009614
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	16.8201792	Cubic Meter	7622.8680814	128218.00714711

Total Amount:	291034.18112939
----------------------	-----------------

Provision for Contingency (+) @	3000
---------------------------------	------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	965.8
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.98112939
----------------------	-----------------

Grand Net Total Amount	299999.98112939
-------------------------------	-----------------

MADHUSMITA MOHANTY
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block