

Estimate Abstract

OD/369/3538/275134/408773/00069828 : CONST. OF CC ROAD FROM NISANKA SAHI PMGST ROAD TO  
HARIJAN SAHI KOTHAGHARA  
Block : Delanga, Gram Panchayat : Khelaur  
Created By: LOPAMUDRA PATI

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	64.73743	Cubic Meter	7485.92009878	484619.22838036

<b>Total Amount:</b>	484619.22838036
----------------------	-----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	5000
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	499619.22838036
----------------------	-----------------

<b>Grand Net Total Amount</b>	499619.22838036
-------------------------------	-----------------

LOPAMUDRA PATI  
JE  
Delanga Block

SUBRAT KUMAR BARIK  
AEE  
Delanga Block

PuriDelangaBDO  
BDO  
Delanga Block