

Estimate Abstract

**OD/346/3305/116237/393141/00065368 : repair and restoration of road from PWD eroad to Prasanta Barik house
Block : Nilgiri, Gram Panchayat : Dhobasila
Created By:BAIDYANATH SINGH**

SI No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	6.0110905010849	Cubic Meter	7678.7607744	46157.725951099
2	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	3.87962928	Square Meter	216.23489289764	838.91122184335

Total Amount:	46996.637172943
----------------------	-----------------

Provision for Contingency (+) @	480
Display Citizen Board (+) @	523
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	47999.637172943
----------------------	-----------------

Grand Net Total Amount	47999.637172943
-------------------------------	-----------------

**BAIDYANATH SINGH
JE
Nilgiri Block**

**Sarat kumar Upadhyay
AEE
Nilgiri Block**

**Bikram Kishore Parida
BDO
Nilgiri Block**