

Estimate Abstract

**OD/363/3475/119860/428845/00069508 : Const. of Paver block road at Badakellar village
Block : Laxmipur, Gram Panchayat : Kusumguda
Created By:GIRIJA SANKAR PATI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.0328	Cubic Meter	981.824232	17705.04001081
2	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	10	Square Meter	216.23489289764	2162.3489289764
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.0322	Cubic Meter	5351.8789606	59042.999069131
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	4.186	Cubic Meter	7052.5478262	29521.965200473
5	Earth Work : AR0103aa (Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department			
	51.11085	Cubic Meter	375.4984464	19192.044769183
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	230.645	Square Meter	635.85	146655.62325

Total Amount:	274280.02122857
----------------------	-----------------

Provision for Contingency (+) @	6400
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	34319.9
Provision for survey investigation and quality control (+) @	

Total Amount:	319999.92122857
----------------------	-----------------

Grand Net Total Amount	319999.92122857
-------------------------------	-----------------

GIRIJA SANKAR PATI
JE
Laxmipur Block

MUVALA PAWAN KUMAR
AEE
Laxmipur Block

SABYASACHI BEHERA
BDO
Laxmipur Block