

Estimate Abstract

**OD/346/3305/116237/393148/00068407 : Construction of CC road from Dayanidhi Mallik house to Harihar Mallik house in village Dhobasila.
Block : Nilgiri, Gram Panchayat : Dhobasila
Created By:BAIDYANATH SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.457347488	Cubic Meter	240.77592	1073.2219421829
2	Earth Work : AR0115a (Filling foundation and plinth with crusher dust well watered and rammed) : Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.58648490688	Cubic Meter	1249.565132	23225.023466082
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.915291816	Cubic Meter	6246.6913492	136898.0638022
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.994673688	Cubic Meter	7678.7607744	122819.27291474
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	38.99696328	Square Meter	216.23489289764	8432.504178184

Total Amount:	292448.08630339
----------------------	-----------------

Provision for Contingency (+) @	2551
---------------------------------	------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.08630339
----------------------	-----------------

Grand Net Total Amount	299999.08630339
-------------------------------	-----------------

BAIDYANATH SINGH
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block