

Estimate Abstract

OD/365/3507/120347/387951/00064208 : Construction of Drain from Ashok Mohanta house to Smasan road at Chaulagheri
Block : Saraskana, Gram Panchayat : Jharpokharia
Created By:JAYANTA KUMAR BAG

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	39.06	Cubic Meter	240.77592	9404.7074352
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.765	Cubic Meter	1090.793132	10651.59493398
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.483	Cubic Meter	6146.0296588	132035.15516
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	2.604	Cubic Meter	7675.7839206	19987.741329242
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	78.12	Square Meter	216.39264180804	16904.593178044
6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	39.06	Square Meter	194.699541634	7604.964096224

Total Amount:	196588.75613269
----------------------	-----------------

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	2330.24

Total Amount:	201918.99613269
----------------------	-----------------

Grand Net Total Amount	201918.99613269
-------------------------------	-----------------

JAYANTA KUMAR BAG
JE
Saraskana Block

Gagan Bihari Mohanty
AEE
Saraskana Block

Suman Raja Mohanty
BDO
Saraskana Block