

**Estimate Abstract**

**OD/346/3309/116330/393696/00069786 : Repair & Maintenance of Nuagan AWC  
Block : Soro, Gram Panchayat : Singakhunta  
Created By:Chandra Sekhar Mohapatra**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.41340194304	Cubic Meter	240.77592	1303.4168331652
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.74669067904	Cubic Meter	1540.455232	8852.5197232128
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.269772064	Cubic Meter	5991.0259587	43553.393149256
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	4.530688	Cubic Meter	7432.5709009	33674.659789857
5	<b>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	0.11702767104	Cubic Meter	6470.6272098855	757.24243254095
6	<b>R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			

0.56062264	Cubic Meter	12772.511614276	7161.1978062068
7	<b>Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.		
	1.2158384416	Cubic Meter	5370.01463776
8	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.		
	0.54	Quintal	8421.6029474
9	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.		
	10.44880041	Square Meter	258.19446989
10	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.		
	12.20466711	Square Meter	181.594415914
11	<b>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) :</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)		
	2.50094876	Square Meter	1023.264564825
12	<b>Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) :</b> Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.		
	0.99684919	Square Meter	1538.521285616
13	<b>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) :</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.		
	182.97989074	Square Meter	71.84257680551

14	<b>Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) :</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	182.97989074	Square Meter	94.7676397125	17340.572360281
15	<b>Painting : AR0918hk (Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance).) :</b> Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).			
	108.43359451	Square Meter	163.17238623702	17693.368364454
16	<b>Painting : AR0901b (Priming one coat in inner surface with primer of approved quality over iron work.) :</b> Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	45.057955	Square Meter	66.12221647451	2979.3318544087
17	<b>Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) :</b> Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	45.057955	Square Meter	164.24273777702	7400.4418878338

<b>Total Amount:</b>	173945.55469573
----------------------	-----------------

Provision for PH Work (+) @	12000
Provision for EI Work (+) @	
Provision for Contingency (+) @	2000
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	9054.44
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	199999.99469573
----------------------	-----------------

<b>Grand Net Total Amount</b>	199999.99469573
-------------------------------	-----------------

**Chandra Sekhar Mohapatra**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**