

Estimate Abstract

OD/346/3305/116253/393307/00069509 : Repair and restoration of road from Nuasahi road to chandan sahi road via nuasahi jahira

Block : Nilgiri, Gram Panchayat : Telipal

Created By:MADHUSMITA MOHANTY

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	0.897076224	Cubic Meter	240.77592	215.99435314373
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.588304896	Cubic Meter	1118.780232	4014.5245840336
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	7.84844544	Square Meter	216.39264180804	1698.3458428479
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.48538112	Cubic Meter	6237.9868662	27979.748516461
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.153358848	Cubic Meter	7872.5794714	24825.068132722
Total Amount:				58733.681429209
Provision for Contingency (+) @				610

Display Citizen Board (+) @	300
Any Other Lumpsum (+) @	1356.31
Provision for survey investigation and quality control (+) @	

Total Amount:	60999.991429209
----------------------	-----------------

Grand Net Total Amount	60999.991429209
-------------------------------	-----------------

MADHUSMITA MOHANTY
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block