

**Estimate Abstract**

**OD/347/3320/116544/379785/00063697 : Improvement of Road at Barpali  
Block : Paikmal, Gram Panchayat : Kansada  
Created By: Bijepi Bag**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.832	Cubic Meter	240.77592	681.87740544
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.921	Cubic Meter	708.124332	9149.674493772
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.753	Cubic Meter	5578.35296346	87875.794233385
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	12.921	Cubic Meter	7190.65692502	92910.478128183
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	41.4	Square Meter	216.39264180804	8958.6553708529

<b>Total Amount:</b>	199576.47963163
----------------------	-----------------

Provision for Contingency (+) @	423
Display Citizen Board (+) @	1000

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	200999.47963163
----------------------	-----------------

<b>Grand Net Total Amount</b>	200999.47963163
-------------------------------	-----------------

**Bijepi Bag  
JE  
Paikmal Block**

**Ranjan Kumar Nayak  
AEE  
Paikmal Block**

**BDO Paikmal  
BDO  
Paikmal Block**