

**Estimate Abstract**

**OD/356/3403/118498/400567/00071246 : Const. of Paver Block Road from Pyarimohan Jarika Pokhari to  
Jogendra House  
Block : Sukinda, Gram Panchayat : Gobarghati  
Created By:Ratnakar Sahoo**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.42	Cubic Meter	240.77592	2990.4369264
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.185	Cubic Meter	949.100232	23903.08934292
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.56	Cubic Meter	5858.05773766	97009.43613565
4	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	251.85	Square Meter	634.878	159894.0243
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	49.68	Square Meter	216.23489289764	10742.549479155

<b>Total Amount:</b>	294539.53618412
----------------------	-----------------

Provision for Contingency (+) @	2945.3953618412
---------------------------------	-----------------

Display Citizen Board (+) @	2500
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299984.93154597
----------------------	-----------------

<b>Grand Net Total Amount</b>	299984.93154596
-------------------------------	-----------------

**Ratnakar Sahoo**  
**JE**  
**Sukinda Block**

**Asish Kumar Biswal**  
**AEE**  
**Sukinda Block**

**Prangyan Primita Prusty**  
**BDO**  
**Sukinda Block**