

**Estimate Abstract**

**OD/370/3549/121134/426845/00065342 : Const of CC Road at Gambhari  
Block : Gudari, Gram Panchayat : Karlaghati  
Created By:P Mohan Rao Patro**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	96.3	Cubic Meter	240.77592	23186.721096
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.55	Cubic Meter	526.617232	4502.5773336
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.25	Cubic Meter	5240.88898192	153296.00272116
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.84	Cubic Meter	6819.24215304	108016.79570415
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	27	Square Meter	216.39264180804	5842.6013288171

<b>Total Amount:</b>	294844.69818373
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	2155

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.69818373
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.69818373
-------------------------------	-----------------

**P Mohan Rao Patro**  
**JE**  
**Gudari Block**

**Sasmita Sabar**  
**AEE**  
**Gudari Block**

**SUCHISMITA BEHERA**  
**BDO**  
**Gudari Block**