

Estimate Abstract

**OD/365/3488/120075/387443/00067257 : Construction of Culvert near forest building at Rangamatia
Block : Bahalda, Gram Panchayat : Jashipur
Created By:PRAFULLA KUMAR BED**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	27.60888	Cubic Meter	240.77592	6647.5534821696
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.928956	Cubic Meter	701.135132	2754.7290836822
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.888744816	Cubic Meter	5621.9633838	123057.72187289
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.1468304	Cubic Meter	7197.4789276	8254.2876375311
5	R.C.C. Work : AR0401 (R.C.C work) : Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)			
	4.088238	Cubic Meter	7197.4789276	29425.006856014
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	1.85	Quintal	8428.8790379	15593.426220115

7	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	40.87360388	Square Meter	216.23489289764	8838.2993573324
8	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	9.054790895	Square Meter	172.692698296	1563.6962721636

Total Amount:	196134.7207819
----------------------	----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	1365
Display Citizen Board (+) @	2500
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.7207819
----------------------	----------------

Grand Net Total Amount	199999.7207819
-------------------------------	----------------

PRAFULLA KUMAR BED
JE
Bahalda Block

MADAN MOHAN NAIK
AEE
Bahalda Block

MayurbhanjBahaldaBDO
BDO
Bahalda Block