

Estimate Abstract

OD/361/3449/119384/387180/00069543 : const. of cc road from daitary mohapatra house to chintamani house at ambo village

Block : Hatadihi, Gram Panchayat : Ambo

Created By:KSHETRAMOHAN MARNDI

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) : Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	192.5	Square Meter	4.6662	898.2435
2	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	19.25	Cubic Meter	240.77592	4634.93646
3	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.25	Cubic Meter	1044.403832	20104.773766
4	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.25	Cubic Meter	6058.20545624	116620.45503262
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	16.275	Cubic Meter	7516.99679888	122339.12290177
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	22	Square Meter	216.23489289764	4757.1676437481

Total Amount:	269354.69930414
----------------------	-----------------

Provision for Contingency (+) @	2693.5469930414
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	1951.75
Provision for survey investigation and quality control (+) @	

Total Amount:	274999.99629718
----------------------	-----------------

Grand Net Total Amount	274999.99629718
-------------------------------	-----------------

KSHETRAMOHAN MARNDI
JE
Hatadihi Block

MONALISHA NAIK
AEE
Hatadihi Block

RANJAN KUMAR PARIDA
BDO
Hatadihi Block