

Estimate Abstract

**OD/363/3476/119876/429882/00067900 : Const. of CC with Paver Block road at Hikimput Near BNRGSK Building
Block : Nandapur, Gram Panchayat : Hikimput
Created By:GOPAL MINZ**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.61975	Cubic Meter	240.77592	2075.42823642
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.6675	Cubic Meter	782.551232	19303.58251536
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.50625	Cubic Meter	5644.8435198	19792.232591299
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	19.3455	Cubic Meter	7127.8243786	137891.32651621
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	32.815	Square Meter	216.23489289764	7095.7480104361
6	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	225	Square Meter	629.931	141734.475

Total Amount:	327892.79286972
----------------------	-----------------

Provision for Contingency (+) @	2199
Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	333091.79286972
----------------------	-----------------

Grand Net Total Amount	333091.79286972
-------------------------------	-----------------

GOPAL MINZ
JE
Nandapur Block

JHASKETAN BEHERA
AEE
Nandapur Block

DURGA PRASADA DORA
BDO
Nandapur Block