

Estimate Abstract

**OD/346/3304/116218/393521/00070091 : Improvement of road with CC/Gr-II Metalling from Makunda patra house to Baikuntha Biswal at Kupari.
Block : Khaira, Gram Panchayat : Kupari
Created By:Annapura Ghadei**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.12625	Cubic Meter	240.77592	511.9497999
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.89875	Cubic Meter	1493.995232	13294.69007076
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.4425	Cubic Meter	6928.2801027	86205.125177845
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	9.6075	Cubic Meter	8311.2466609	79850.302294597
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	25.2	Square Meter	216.23489289764	5449.1193010205
Total Amount:			185311.18664412	
Provision for Contingency (+) @			220.8	

Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	186531.98664412
----------------------	-----------------

Grand Net Total Amount	186531.98664412
-------------------------------	-----------------

Annapurna Ghadei
JE
Khaira Block

Uttam Ku Sahoo
AEE
Khaira Block

Narayan Sahu
BDO
Khaira Block