

Estimate Abstract

**OD/373/3580/121634/384373/00069937 : Construction of Cement Concrete Road from Sarat House to P Pattnaik House Near C T School Kuarmunda
Block : Kuarmunda, Gram Panchayat : Kuarmunda
Created By:bharatsahoo**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	32.56	Cubic Meter	240.77592	7839.6639552
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.9125	Cubic Meter	893.227032	28505.1076587
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.785	Cubic Meter	5358.72947952	159609.7575475
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	27.01	Cubic Meter	6831.15704224	184509.5517109
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	44.4	Square Meter	216.23489289764	9600.8292446552
Total Amount:				390064.91011696
Provision for Contingency (+) @				4000

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	934

Total Amount:	399998.91011696
----------------------	-----------------

Grand Net Total Amount	399998.91011696
-------------------------------	-----------------

bharatsahoo
JE
Kuarmunda Block

ChaitanyaHembram
AEE
Kuarmunda Block

BDO Kuarmunda
BDO
Kuarmunda Block