

**Estimate Abstract**

**OD/356/3397/118361/401278/00072550 : Const Of Paver Road From Deulei To Village totakana  
Block : Dharmasala, Gram Panchayat : Samparu  
Created By:SANTOSHI PANDA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	14.2125	Cubic Meter	240.77592	3422.027763
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	40.3635	Cubic Meter	853.049232	34432.052675832
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.475	Cubic Meter	5605.75221316	47508.750006531
4	<b>R.C.C. Work : AR0401 (R.C.C work) :</b> Reinforced cement concrete (1:2:4) work with 12mm size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (To be used for minor repair work only)			
	9.94875	Cubic Meter	7139.89734492	71033.053710273
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	79.59	Square Meter	216.23489289764	17210.135125723
6	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	346.785	Square Meter	632.025	219176.789625

<b>Total Amount:</b>	392782.80890636
----------------------	-----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	3217.19
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	399999.99890636
----------------------	-----------------

<b>Grand Net Total Amount</b>	399999.99890636
-------------------------------	-----------------

**SANTOSHI PANDA**  
**JE**  
**Dharmasala Block**

**LINGARAJ PANDA**  
**AEE**  
**Dharmasala Block**

**Jyotirmaya Kar**  
**BDO**  
**Dharmasala Block**