

Estimate Abstract

**OD/348/3323/116632/394730/00016217 : Improvement Of Road From Dhinda Sahi Road To Ram Mandir,
Jagadalapur G.P.
Block : Bhadrak, Gram Panchayat : Jagadalpur
Created By:GOBINDA CHANDRA PRADHAN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.26	Cubic Meter	240.77592	303.3776592
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.4	Cubic Meter	1188.611632	9984.3377088
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.66	Cubic Meter	6543.39812606	63209.22589774
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	28	Square Meter	216.23489289764	6054.5770011339
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	7.56	Cubic Meter	7959.30098222	60172.315425583

Total Amount:	139723.83369246
----------------------	-----------------

Provision for Contingency (+) @	1397.2383369246
---------------------------------	-----------------

Display Citizen Board (+) @	1500
Any Other Lumpsum (+) @	1166
Provision for survey investigation and quality control (+) @	

Total Amount:	143787.07202938
----------------------	-----------------

Grand Net Total Amount	143787.07202938
-------------------------------	-----------------

GOBINDA CHANDRA PRADHAN
JE
Bhadrak Block

GOBIND CHANDRA BEHERA
AEE
Bhadrak Block

RASMI RANJAN MALLICK
BDO
Bhadrak Block