

Estimate Abstract

**OD/359/3425/118920/415805/00070486 : Improvement of road from Abhinash house to Bipra house.
Block : G.Udayagiri, Gram Panchayat : Ratingia
Created By:CHAKRADHAR PURTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	17.514	Cubic Meter	240.77592	4216.94946288
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.4595	Cubic Meter	579.298832	845.486645304
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	27.897	Cubic Meter	5699.81035994	159007.60961125
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	2.15985	Cubic Meter	8389.53296078	18120.132765341
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	42.6615	Square Meter	216.55039071844	9238.3644936347

Total Amount:	191428.54297841
----------------------	-----------------

Provision for Contingency (+) @	2500
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	1071
Provision for survey investigation and quality control (+) @	
Total Amount:	199999.54297841
Grand Net Total Amount	199999.54297841

CHAKRADHAR PURTY
JE
G.Udayagiri Block

ASIT KUMAR SETHY
AEE
G.Udayagiri Block

Sarata Kumar Mallik
BDO
G.Udayagiri Block