

**Estimate Abstract**

**OD/359/3424/118910/417496/00065794 : Const. of Paver road at Manikjodi  
Block : Daringibadi, Gram Panchayat : Sirkabarga  
Created By:KAMAL PATRO**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	19.116	Cubic Meter	240.77592	4602.67248672
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.6025	Cubic Meter	645.049832	15224.78865978
3	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	143.55	Square Meter	625.8468	89840.30814
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.980264	Cubic Meter	7945.94808128	63410.763418908
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	34.6968	Square Meter	216.39264180804	7508.1322142852

<b>Total Amount:</b>	180586.66491969
----------------------	-----------------

Provision for Contingency (+) @	1805.8666491969
---------------------------------	-----------------

Display Citizen Board (+) @	3925
Any Other Lumpsum (+) @	15720
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	202037.53156889
----------------------	-----------------

<b>Grand Net Total Amount</b>	202037.53156889
-------------------------------	-----------------

**KAMAL PATRO**  
JE  
Daringibadi Block

**SANJAYA KUMAR RATH**  
AEE  
Daringibadi Block

**PRITI RANJAN RATH**  
BDO  
Daringibadi Block