

**Estimate Abstract**

**OD/356/3397/118337/401391/00071764 : Construction Of Saluani Community Centre  
Block : Dharmasala, Gram Panchayat : Endalba  
Created By:PRADOSH RANJAN DASH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	20.997	Cubic Meter	240.77592	5055.57199224
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.94	Cubic Meter	515.507232	8732.69251008
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.92875	Cubic Meter	5623.56250266	33340.696187645
4	<b>R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	3.24	Cubic Meter	6200.9978895747	20091.233162222
5	<b>R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			
	1.659375	Cubic Meter	6957.8200147164	11545.63258692
6	<b>R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			

2.940625	Cubic Meter	14256.751276895	41923.759223619
7	<b>R.C.C. Work : AR0404Ad (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)		
	1.99125	Cubic Meter	12865.282118105
8	<b>R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)		
	4.576875	Cubic Meter	12532.470243965
9	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.		
	14	Quintal	8442.477183
10	<b>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.		
	4.764375	Cubic Meter	5047.558051088
11	<b>Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.		
	8.293125	Cubic Meter	5080.888051088
12	<b>Iron Work : AR1704 (Iron Doors and windows fixing) :</b> Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.		
	2.16	Quintal	15784.618167087
13	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.		
	40.26	Square Meter	171.0119913532

14	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.)</b> : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	66.945	Square Meter	245.496359222	16434.753768117
15	<b>Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over masonry work in inside.)</b> : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	30.87	Square Meter	269.2167339776	8310.7205778885
16	<b>Other Building Items. : AR1901Ba (Vitrified Tile 600mmx600mm Coloured /Printed)</b> : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.			
	34.65	Square Meter	1053.1948692326	36493.20221891
17	<b>Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer)</b> : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)			
	40	Square Meter	160.24105073419	6409.6420293676
18	<b>Painting : AR0922b (Finishing wall surface with two coats with distemper of approved shades above one coat waterbound Primer on new work (Inside))</b> : Finishing wall surface with two coats with distemper of approved shades above one coat waterbound Primer for new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	60	Square Meter	150.47727961951	9028.6367771706
19	<b>Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface)</b> : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	14.22	Square Meter	229.62828514803	3265.314214805

<b>Total Amount:</b>	508968.69569763
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	10730
Provision for Contingency (+) @	5300

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	529998.69569763
----------------------	-----------------

<b>Grand Net Total Amount</b>	529998.69569763
-------------------------------	-----------------

**PRADOSH RANJAN DASH**  
JE  
Dharmasala Block

**LINGARAJ PANDA**  
AEE  
Dharmasala Block

**Jyotirmaya Kar**  
BDO  
Dharmasala Block