

Estimate Abstract

**OD/363/3479/119913/429976/00072780 : Construction of CC road from RD road to Kumarguda
Block : Semiliguda, Gram Panchayat : Charangul
Created By:SMT PREETIMAYEE PANIGRAHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	15.341	Cubic Meter	240.77592	3693.74338872
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.1	Cubic Meter	586.560732	15309.2351052
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	67.541	Cubic Meter	5555.2585903	375207.72044745
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	66.7	Square Meter	216.55039071844	14443.91106092
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	39.15	Cubic Meter	7050.3420771	276020.89231846

Total Amount:	684675.50232076
----------------------	-----------------

Provision for Contingency (+) @	7000
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	3324
Provision for survey investigation and quality control (+) @	
Total Amount:	699999.50232076
Grand Net Total Amount	699999.50232076

SMT PREETIMAYEE PANIGRAHI
JE
Semiliguda Block

ER TOPHAN KUMAR NAYAK
AEE
Semiliguda Block

JASHMIN KUMAR PRADHAN
BDO
Semiliguda Block