

**Estimate Abstract**

**OD/363/3471/119802/428918/00069497 : Construction of Paver block road from RD road to GP office  
Block : Koraput, Gram Panchayat : Kendar  
Created By:Sanjay Kumar Prusty**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	103.77675	Cubic Meter	240.77592	24986.94245586
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	58.4025	Cubic Meter	712.760232	41626.97944938
3	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	530.115	Square Meter	627.858	332836.94367
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	16.173	Cubic Meter	7343.1281491	118760.41155539
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	107.82	Square Meter	216.86588853924	23382.480102301
<b>Total Amount:</b>			541593.75723294	
Provision for Contingency (+) @			5415.9375723294	

Display Citizen Board (+) @	2990
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	549999.69480526
----------------------	-----------------

<b>Grand Net Total Amount</b>	549999.69480527
-------------------------------	-----------------

**Sanjay Kumar Prusty**  
**JE**  
**Koraput Block**

**PHAKIR MOHAN PRADHAN**  
**AEE**  
**Koraput Block**

**Dr. DEBASIS GOUDA**  
**BDO**  
**Koraput Block**