

Estimate Abstract

**OD/363/3479/119917/429848/00069367 : CC Drain at Paraja sahi to Gadaba sahi of Bhitardusura
Block : Semiliguda, Gram Panchayat : Hataguda
Created By:SMT SWARNAPRAVA NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	50.5	Cubic Meter	240.77592	12159.18396
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.05	Cubic Meter	979.804232	4948.0113716
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.05	Cubic Meter	5627.0332303	28416.517813015
4	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	22.725	Cubic Meter	6161.5955153375	140022.25808604
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	20.4525	Quintal	8448.6840774	172796.71109302

Total Amount:	358342.68232368
----------------------	-----------------

Provision for PH Work (+) @	
-----------------------------	--

Provision for EI Work (+) @	
Provision for Contingency (+) @	3583.4268232368
Display Citizen Board (+) @	5273.5
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	367199.60914692
----------------------	-----------------

Grand Net Total Amount	367199.60914692
-------------------------------	-----------------

SMT SWARNAPRAVA NAIK
JE
Semiliguda Block

ER TOPHAN KUMAR NAYAK
AEE
Semiliguda Block

JASHMIN KUMAR PRADHAN
BDO
Semiliguda Block