

Estimate Abstract

**OD/346/3305/116237/393140/00068403 : Construction of CC drain from Harish Chandra Barik house to Rajendra Biswal house
Block : Nilgiri, Gram Panchayat : Dhobasila
Created By:BAIDYANATH SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	65.5817088	Cubic Meter	240.77592	15790.496271492
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.213987968	Cubic Meter	1184.531232	8545.1940553682
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.213987968	Cubic Meter	6246.6913492	45063.556232938
4	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	15.411701568	Cubic Meter	6393.925626724	98541.273607058
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	3.8	Quintal	8427.9076199	32026.04895562
6	R.C.C. Work : AR0410f (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters			
	100.4095624	Square Meter	934.29150984209	93811.80165728

Total Amount:	293778.37077976
----------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	1221

Total Amount:	299999.37077976
----------------------	-----------------

Grand Net Total Amount	299999.37077976
-------------------------------	-----------------

BAIDYANATH SINGH
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block