

**Estimate Abstract**

**OD/363/3478/119908/430078/00069201 : Development of Amrit Sarovar at Jamuguda.  
Block : Pottangi, Gram Panchayat : Pukali  
Created By:PRASANNA GARADA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	509.7	Cubic Meter	240.77592	122723.486424
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.5	Cubic Meter	1134.435232	5104.958544
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.4	Cubic Meter	5754.2388418	117386.47237272
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	3	Cubic Meter	7256.3967726	21769.1903178
5	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	90	Square Meter	640.383	57634.47
6	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	72	Square Meter	217.02363744964	15625.701896374

<b>Total Amount:</b>	340244.27955489
----------------------	-----------------

Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	2000
Provision for survey investigation and quality control (+) @	755
Provision for Contingency (+) @	3000

<b>Total Amount:</b>	349999.27955489
----------------------	-----------------

<b>Grand Net Total Amount</b>	349999.27955489
-------------------------------	-----------------

**PRASANNA GARADA**  
**JE**  
**Pottangi Block**

**ER TOPHAN KUMAR NAYAK**  
**AEE**  
**Pottangi Block**

**RAMKRISHNA NAYAK**  
**BDO**  
**Pottangi Block**