

**Estimate Abstract**

**OD/363/3479/119921/429897/00070412 : Const. of CC road at Lenjiguda of P. Muthai GP  
Block : Semiliguda, Gram Panchayat : Parajamuthai  
Created By:SMT MITANJALI DAS**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.9872	Cubic Meter	240.77592	478.469908224
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.512	Cubic Meter	586.560732	6165.926414784
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.4992	Cubic Meter	5515.4614795	68938.856124566
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.884	Cubic Meter	7028.6408535	55413.804488994
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	27.36	Square Meter	216.9289881034	5935.177114509

<b>Total Amount:</b>	136932.23405108
----------------------	-----------------

Provision for Contingency (+) @	1440
Display Citizen Board (+) @	3975

Any Other Lumpsum (+) @	1440
Provision for survey investigation and quality control (+) @	
<b>Total Amount:</b>	143787.23405108
<b>Grand Net Total Amount</b>	143787.23405108

**SMT MITANJALI DAS**  
**JE**  
**Semiliguda Block**

**ER TOPHAN KUMAR NAYAK**  
**AEE**  
**Semiliguda Block**

**JASHMIN KUMAR PRADHAN**  
**BDO**  
**Semiliguda Block**