

**Estimate Abstract**

**OD/369/3541/120970/410112/00074182 : Const. of CC Road from Badal Sub Center to Road  
Block : Kanas, Gram Panchayat : Badal  
Created By:JAGANNATH ROUT**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.455	Cubic Meter	240.77592	1072.6567236
2	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	16.236	Cubic Meter	7546.73760228	122528.83171062
3	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	23.1	Square Meter	216.39264180804	4998.6700257657
4	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.315	Cubic Meter	1065.310832	19511.16788808
5	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.255	Cubic Meter	6049.91135644	146740.59995045

<b>Total Amount:</b>	294851.92629852
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	2148

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.92629852
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.92629852
-------------------------------	-----------------

**JAGANNATH ROUT**  
**JE**  
**Kanas Block**

**SASWAT KUMAR SENAPATI**  
**AEE**  
**Kanas Block**

**SOUMYA RANJAN SWAIN**  
**BDO**  
**Kanas Block**