

Estimate Abstract

**OD/358/3419/118819/422634/00071205 : Construction of Guard wall at Dumerpali
Block : Madanpur Rampur, Gram Panchayat : Nunpur
Created By:JE PRABIN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	24.42	Cubic Meter	240.77592	5879.7479664
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.0525	Cubic Meter	550.857232	1681.49170068
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	66.6	Square Meter	216.39264180804	14411.749944415
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.2525	Cubic Meter	5207.6157318	131505.31626728
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	0.4995	Cubic Meter	7300.6767886	3646.6880559057

Total Amount:	157124.99393468
----------------------	-----------------

Display Citizen Board (+) @	1303
Any Other Lumpsum (+) @	

Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	1571.2499393468
Total Amount:	159999.24387403
Grand Net Total Amount	159999.24387403

JE PRABIN
JE
Madanpur Rampur Block

AEE MRAMPUR
AEE
Madanpur Rampur Block

Sharat Kumar Sethi
BDO
Madanpur Rampur Block