

**Estimate Abstract**

**OD/348/3323/116621/394794/00072015 : Imp. of Road with from Berhampur RD Road to Hari Giri House of  
WardNo No. 5  
Block : Bhadrak, Gram Panchayat : Berhamopur  
Created By:SATYAJIT MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	2.3625	Cubic Meter	240.77592	568.833111
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.48125	Cubic Meter	1258.402632	9414.42469065
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.63125	Cubic Meter	6546.04639656	69592.655753428
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.875	Cubic Meter	7968.28730572	62750.262532545
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	21	Square Meter	216.55039071844	4547.5582050872
<b>Total Amount:</b>				146873.73429271
Provision for Contingency (+) @				1468.7373429271

Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	657.52
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	149999.99163564
----------------------	-----------------

<b>Grand Net Total Amount</b>	149999.99163564
-------------------------------	-----------------

**SATYAJIT MOHANTY**  
**JE**  
**Bhadrak Block**

**GOBIND CHANDRA BEHERA**  
**AEE**  
**Bhadrak Block**

**RASMI RANJAN MALLICK**  
**BDO**  
**Bhadrak Block**