

Estimate Abstract

**OD/355/3386/118067/398208/00073238 : Construction of Similigosein CRC
Block : Balikuda, Gram Panchayat : Tandikula
Created By:SANJAY KUMAR KALLO**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	11.8512	Cubic Meter	240.77592	2853.483583104
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.4508	Cubic Meter	741.302832	1075.4821486656
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.9752	Cubic Meter	6462.13193228	12764.002992639
4	R.C.C. Work : AR0404Bg (Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).) : Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).			
	3.8275	Cubic Meter	13280.394572072	50830.710224606
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	3.5	Quintal	8421.1581636	29474.0535726
Total Amount:			96997.732521615	

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	1000
Display Citizen Board (+) @	1500
Any Other Lumpsum (+) @	502
Provision for survey investigation and quality control (+) @	

Total Amount:	99999.732521615
----------------------	-----------------

Grand Net Total Amount	99999.732521615
-------------------------------	-----------------

SANJAY KUMAR KALLO
JE
Balikuda Block

DIPTI REKHA MALLICK
AEE
Balikuda Block

Sagar Kumar Nanda
BDO
Balikuda Block