

Estimate Abstract

**OD/361/3451/119443/385297/00068257 : REPAIR AND MAINTENANCE OF DHABALESWAR HIGH SCHOOL,
DEOJHAR
Block : Joda, Gram Panchayat : Deojhar
Created By:SARITA ROUT**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)			
	66.31323237	Square Meter	794.2769332722	52671.07084221
2	Painting : AR0918hk (Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance).) : Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).			
	1177.3668539504	Square Meter	163.1982441104	192144.20323849

Total Amount:	244815.2740807
----------------------	----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	2480
Display Citizen Board (+) @	704
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	247999.2740807
----------------------	----------------

Grand Net Total Amount	247999.2740807
-------------------------------	----------------

SARITA ROUT
JE
Joda Block

AJAYA KUMAR SAHOO
AEE
Joda Block

KendujharJodaBDO
BDO
Joda Block