

Estimate Abstract

**OD/346/3307/116267/392844/00072708 : Const. of CC Road from Sana Rout House to Gopal Behera House Vill
Mandagan
Block : Remuna, Gram Panchayat : Barunasing
Created By:MAHENDRA KUMAR SAMAL**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.2	Cubic Meter	240.77592	288.931104
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.6	Cubic Meter	1149.171132	28269.6098472
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.7	Cubic Meter	6012.0142132	124448.69421324
4	Concrete : AR0307 (First floor) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.3	Cubic Meter	8027.5880094	122822.09654382
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	60	Square Meter	216.23489289764	12974.093573858

Total Amount:	288803.42528212
----------------------	-----------------

Provision for Contingency (+) @	3000
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	3196.57
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.99528212
Grand Net Total Amount	299999.99528212

MAHENDRA KUMAR SAMAL
JE
Remuna Block

AJAY KUMAR BEHERA
AEE
Remuna Block

Sourav Sarthak Mohapatra
BDO
Remuna Block