

Estimate Abstract

**OD/370/3547/121124/425349/00069218 : REPAIR AND MAINTANANCE OF UP SCHOOL DARUKONA
Block : Bissamcuttack, Gram Panchayat : Sahada
Created By:SAGAR GOUDA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Dismantling : AR1620 (Dismantling and removing 2.5 cm thick grading concrete from roof) : Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	54.825	Square Meter	112.89193548387	6189.3003629032
2	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge. (Old Work)			
	54.825	Square Meter	733.0242596976	40188.055037921
3	Dismantling : AR1613 (Removing old lime or cement plaster) : Removing old lime or cement plaster from walls including raking out joints 12 mm deep and removing the debris within 50m lead and as per direction of Engineer-in-Charge.			
	127.38	Square Meter	50.174193548387	6391.1887741935
4	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	129.78	Square Meter	242.936882064	31528.348554266
5	Painting : AR0901a (Priming one coat in inner surface with primer of approved quality over woodwork) : Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	182.8025	Square Meter	70.08994432871	12812.617048149
6	Painting : AR0919 (Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside)) : Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	182.8025	Square Meter	61.22776449	11192.588418183

7	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.		
	6.5565	Cubic Meter	5227.50850192
8	Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)		
	47.29	Square Meter	1006.4351634082
9	Painting : AR0903i (Painting two coats of enamel paint in outer surface paint (outer surface)) : Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)		
	11.745	Square Meter	164.23523221452

Total Amount:	192099.51936839
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	1920.9951936839
Display Citizen Board (+) @	2000
Any Other Lumpsum (+) @	3978
Provision for survey investigation and quality control (+) @	

Total Amount:	199998.51456207
----------------------	-----------------

Grand Net Total Amount	199998.51456207
-------------------------------	-----------------

SAGAR GOUDA
JE
Bissamcuttack Block

SRI RAMESH CHANDRA SAHU
AEE
Bissamcuttack Block

SRI SIBA PRASAD PATNAIK
BDO
Bissamcuttack Block