

Estimate Abstract

**OD/352/3356/117431/402288/00074058 : CONSTRUCTION OF CC ROAD FROM BANDHSAHI SCHOOL PAKHA
LAXMIDHAR BISWAL HOUSE TO JAMBESWAR NAIK HOUSE
Block : Parajang, Gram Panchayat : Patarpada
Created By:JYotirmayee biswal**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.20425	Cubic Meter	240.77592	1253.05808166
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.23875	Cubic Meter	1392.146832	28175.31169614
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	34.213125	Cubic Meter	6324.25697166	216372.59430353
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	28.1415	Cubic Meter	7747.14363442	218016.24258803
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	69.39	Square Meter	216.23489289764	15004.539218167
Total Amount:				478821.74588752
Provision for Contingency (+) @				5000

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	11178.23
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.97588752
----------------------	-----------------

Grand Net Total Amount	499999.97588752
-------------------------------	-----------------

JYotirmayee biswal
JE
Parajang Block

Rani panda
AEE
Parajang Block

Sauvagya Behera
BDO
Parajang Block