

Estimate Abstract

**OD/346/3304/116213/393558/00074723 : Const. of CC road from Mahendra Giri house to Sanatan Giri House
Block : Khaira, Gram Panchayat : Jalada
Created By:Santosh Kumar Prusty**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.4425	Cubic Meter	240.77592	828.8711046
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.4075	Cubic Meter	1661.251232	23934.47712504
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.145	Cubic Meter	6731.2476867	135600.98464857
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.555	Cubic Meter	8315.5007809	129347.6146469
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	40.8	Square Meter	216.23489289764	8822.3836302237

Total Amount:	298534.33115533
----------------------	-----------------

Provision for Contingency (+) @	465.65
Display Citizen Board (+) @	1000

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.98115533
----------------------	-----------------

Grand Net Total Amount	299999.98115533
-------------------------------	-----------------

Santosh Kumar Prusty
JE
Khaira Block

Bibhuti Bhusan Nayak
AEE
Khaira Block

Narayan Sahu
BDO
Khaira Block