

**Estimate Abstract**

**OD/366/3519/120529/427764/00071772 : Development of Road at Kadamguda to Palpur  
Block : Papadahandi, Gram Panchayat : Sirisi  
Created By:GUNANIDHI KUMARA JE**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0110 (Fine dressing of earth work in ordinary or hard soil in road formation) :</b> Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.			
	345.6	Square Meter	4.6662	1612.63872
2	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.68	Cubic Meter	240.77592	1849.1590656
3	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	32.64	Cubic Meter	550.857232	17979.98005248
4	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	40.32	Cubic Meter	5455.9021128	219981.9731881
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	34.56	Cubic Meter	6968.1185326	240818.17648666
6	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	48	Square Meter	216.39264180804	10386.846806786

<b>Total Amount:</b>	492628.77431962
----------------------	-----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	2371
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	499999.77431962
----------------------	-----------------

<b>Grand Net Total Amount</b>	499999.77431962
-------------------------------	-----------------

**GUNANIDHI KUMARA JE**  
**JE**  
**Papadahandi Block**

**Abhimanyu Behera**  
**AEE**  
**Papadahandi Block**

**KAPILDEV SAHU**  
**BDO**  
**Papadahandi Block**